FORM-A

ISO 9001:2008

Centre for Research and Industrial Staff Performance (CRISP)
Shyamla Hills, Opposite Manas Bhawan, Bhopal

OFFER FORM WITH LIST OF ESTIMATE OF SEWAGE LINE WORK CONNECTED FROM NEW GUEST HOUSE BUILDING TO EXISTING SEWAGE CHAMBER OF OLD CRISP,BHOPAL

[HR & ADMINISTRATION DEPARTMENT]

Validity of Rates: Till the Procurement Contract is finally executed

(Name & Seal of Supplier)

Date: _____

CRISP

ISO 9001:2008

FORM-A

Centre for Research and Industrial Staff Performance (CRISP)
Shyamla Hills, Opposite Manas Bhawan, Bhopal

LIST OF ITEMS OF WORK

SOR NO.		PARTICULARS	UNIT	QTY	RATE QUOTED	AMOUNT
19.9	Constructing brick masonry manhole in cement mortar 1:4 (1 cement : 4 sand) R.C.C. top slab with Cement Concrete 1:2:4 mix (1 cement : 2 sand : 4 graded stone aggregate 20 mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 sand : 8 graded stone aggregate 40mm nominal size) inside plastering 12mm thick with cement mortar 1:3 (1 cement : 3 sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 20mm nominal size) finished with a floating coat of neat cement complete as per standard design :					
	19.9.1	Inside size 90x80 cm and 45 cm deep including C.I. cover with frame (light duty) 455x610 mm internal dimensions total weight of cover and frame to be not less than 38 kg (weight of cover 23 kg and weight of frame 15 kg) :				
	19.9.1.1	With well burnt bricks	Each	16		
19.10	Extra for depth for manholes					
	19.10.1	Size 90x80 cm				
	19.10.1.1	With well burnt bricks	Metre	15		
19.23	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix (1 cement : 2 sand : 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement : 3 sand) finished with a floating coat of neat cement and making necessary channels for the drain etc. complete :					
	19.23.1	For pipes 100 to 230 mm diameter	Each	2		

(Name, Signature & Seal of Tenderer)

Date: _____

CRISP

ISO 9001:2008

FORM-A

Centre for Research and Industrial Staff Performance (CRISP)
Shyamla Hills, Opposite Manas Bhawan, Bhopal

SOR NO.		PARTICULARS	UNIT	QTY	RATE QUOTED	AMOUNT
19.4	Providing and laying below ground unplasticised PVC pipe to with stand working pressure of 4 kg/cm2 solid waste pipes confirming to IS:13592 and IS:4985 including jointing with seal ring confirming to IS :5282 leaving 10mm gap for thermal expansion all necessary fittings etc. complete. Excavation to be paid separately.					
	19.4.2	160 mm diameter OD	Rm	133.6		
19.5	Providing and laying cement concrete 1:3:6 (1 cement : 3 sand : 6 graded stone aggregate 20 mm nominal size) all-round PVC. pipes including bed concrete as per standard design:					
	19.5.2	160 mm diameter PVC. pipe	Rm	133.6		
19.8	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 sand) including testing of joints etc. complete :					
	19.8.2	150 mm dia. R.C.C. pipe	Metre	7		
2.9	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m in width or 10 sqm on plan including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50m.					
	2.9.1	Ordinary rock	Cum.			
	2.9.3	Hard rock (blasting prohibited) FOR 16 NO.CHAMBERS	Cum.	17.1		
		Hard rock (blasting prohibited) FOR SEWER LINE	Cum.	137.4		

(Name, Signature & Seal of Tenderer)

Date: _____

CRISP

ISO 9001:2008

FORM-A

Centre for Research and Industrial Staff Performance (CRISP)
Shyamla Hills, Opposite Manas Bhawan, Bhopal

SOR NO.		PARTICULARS	UNIT	QTY	RATE QUOTED	AMOUNT
11.75	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size,design and shape laid in required colour and pattern over and including 50mm thick compacted bed of stone dust, filling the joints with sand etc. all complete as per the direction of Engineer-in-charge.		Sqm	46.5		
NON SOR	Removing and Refixing of existing 60mm thick factory made cement concrete interlocking paver block of M-30 grade , laid in required colour and pattern over and including 50mm thick compacted bed of stone dust, filling the joints with sand etc. all complete as per the direction of Engineer-in-charge.		Each	100		
Extra Item	Dismantling of old structure of the gate. Cleaning of the site also included.		Lump -sum			
IN WORDS RUPEES -- .						

P.S.: Please see the note on page 5 of this list for guidance.

(Name, Signature & Seal of Tenderer)

Date: _____

ISO 9001:2008

FORM-A

Centre for Research and Industrial Staff Performance (CRISP)
Shyamla Hills, Opposite Manas Bhawan, Bhopal

Note for guidance:

1. Please ensure that you are submitting your offer for the item you really deal in. The specifications / Brand name should not be quoted **from our list** unless you have exactly the same item to offer as required by us.

2. The rate that you would mention against an item should be the bare cost **exclusive** of customs / excise duty / VAT / Any other charge. These charges should be shown separately in your bid.

3. Delivery period quoted for an item shall have to be strictly adhered.

4. Your offer shall be subject to the fulfillment of various terms and conditions mentioned in **Annexure of this form.**

5. If a bidder proposes to participate in bids for more than one laboratory; each of such bids shall be kept in separate sealed covers (sealed by adhesive tape at both ends of the cover as also on the back of the envelop where there is a joint.

6. Entry in Col. No. 5 and No. 6 shall be filled in by the bidder / vendor.

7. **All the envelopes containing bids shall then be kept in one single envelope** to be sealed in the same manner as point out in Sr. No. 5 above.

8. **The envelope should be superscribed with "Tender for ……" FOR EXECUTIVE HOSTEL OF CRISP" (NIT No. (……..) dated (……).**

9. **Each page** of the bid including the Annexure **shall be signed and dated by the bidder.**

10. Any damages during the course of excavation shall be the responsibility of the contractor.

11. Payment of bill shall not be made unless 40% of the total cost of the work has been completed and duely verified by our Engineer-In-charge (EIC).

Head of Department
HR & Administration, CRISP

(Name, Signature & Seal of Tenderer)

Date: _____